
of 8

ASTM E 90: Laboratory Measurement of Airborne Sound Transmission of Building Partitions and Elements



Green Glue Company, Client:

L.L.C.

January 11, 2008 Report Date: Test Date: **September 29, 2006** 

Test Number: OL06-0942

RESULT SUMMARY

STC=61

CLIENT **ADDRESS** 

Green Glue Company, L.L.C. 710 11<sup>th</sup> Avenue Northeast West Fargo, ND 58078

Phone: (866) 435-8893

email: info@greengluecompany.com

**ACCREDITATION** 



For the scope of accreditation under NVLAP code 200248-0

**PREPARED BY** 

David M. Berg

Orfield Laboratories, Inc. 2709 East 25<sup>th</sup> Street Minneapolis MN 55406 Voice (612) 721-2455 FAX (612) 721-2457

e-mail dave@orfieldlabs.com

Prepared by:

Reviewed by:

Electronically Reproduced Signatures

Elliott B. Dick

David M. Berg Laboratory Manager **Quality Manager** Signatures are required on this document for an official laboratory test report.

Copies of this document without signatures are for reference only.











Project Sound Transmission

Client Green Glue Company, L.L.C. of 8

Test OL06-0942


Orfield Laboratories Inc

Client Project No. Specimen Green Glue Company OL06-0942

Interior Wall Assembly

Method ASTM Standard E90 Test Date September 29, 2006

# Single Number Rating STC=61



# **Wall Assembly Description**

(listed in order from source room side to reciever room side)

0.625" (5/8") gypsum drywall; 2" Screws @ 12" O.C.

Green Glue @ 58 oz. (2 tubes) per 4x8 sheet (116 oz. total)

0.625" (5/8") gypsum drywall

3-5/8" 25 gauge steel studs @ 24" O.C.

3.5" R13 glass fiber batts

0.625" (5/8") gypsum drywall

Green Glue @ 58 oz. (2 tubes) per 4x8 sheet (116 oz. total)

0.625" (5/8") gypsum drywall; 2" Screws @ 12" O.C.

OL06-0942

Test

Orfield Laboratories Inc

#### SPECIMEN DESCRIPTION

The specimen under test was one interior wall assembly. The elements in the assembly are described below the results table and chart. Additional information regarding the specimen may be found in the appendices.

Test results pertain to this specimen only.

### **INSTALLATION AND DISPOSITION**

Independent contractors fabricated the wall assembly in the specimen opening. Qualified representatives of Orfield Laboratories observed the installation progress, and visually inspected the specimen prior to testing.

#### **TEST METHODS**

The methods followed these published standards:

ASTM E90\*: Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements

ASTM E413: Classification for Rating Sound Insulation

\* Orfield Laboratories, Inc. has been accredited by the U.S. Department of Commerce, National Institute of Standards and Technology (NIST) under their National Voluntary Laboratory Accreditation Program (NVLAP) for this test procedure. This report shall not be used to claim product endorsement by NVLAP or any agency of the U.S. Government.

#### CONFIDENTIALITY

The client has full control over this information and any release of information will be only to the client. The specific testing results are deemed to be confidential exclusively for the client's use. Reproduction of this report, except in full, is prohibited.





Client Green Glue Company, L.L.C. of 8

Orfield Laboratories Inc

Test OL06-0942

# **APPENDIX A: MEASUREMENT SETUP**

Temperature

# **ENVIRONMENT**

Environment 70°F [21.1°C]

Relative Humidity 55%

Specimen Area

Specimen Area 64.5 ft² [5.99 m²]

**Chamber Volume - Airborne Transmission** 

 Source Room Volume
 3284 ft³ [93.0 m³]

 Receiving Room Volume
 8281 ft³ [234.5 m³]

# **INSTRUMENTATION**

Description	Brand	Model	S/N
Microphone	Brüel & Kjær	Type 4134	1478843
Preamplifier	Brüel & Kjær	Type 2639	1202479
Microphone	Brüel & Kjær	Type 4134	558007
Preamplifier	Brüel & Kjær	Type 2639	1312237
Analyzer	Brüel & Kiær	Type 2133	1389369



Client Green Glue Company, L.L.C. of 8

Orfield Laboratories Inc

Test OL06-0942

# **APPENDIX B: CALCULATION RESULTS**

Freq.	Specimen	l	95%	Flanking	STC	
Band	T.L.		Conf. Limit		Defic.	
(Hz)	(dB)		(dB) (dB)		(dB)	
25						
31.5	27.1			40		
40	18.8			47		
50	20.0			43		
63	19.9			43		
80	24.4		±1.63	42		
100	30.7		±1.15	45		
125	37.4	‡	±0.95	46	8	
160	42.8	.‡	±1.27	52	5	
200	47.7	‡	±1.24	53	3	
250	50.9	‡	±0.65	56	3	
315	53.1	.‡	±0.65	60	4	
400	55.6	‡	±0.62	61	4	
500	59.6	‡	±0.40	65	1	
630	61.7	.‡	±0.50	66		
800	63.5	‡	±0.40	69	-	
1000	64.7	‡	±0.25	70	-	
1250	66.4	.‡	±0.25	72		
1600	65.9	‡	±0.32	72	-	
2000	64.7	‡	±0.44	74	-	
2500	66.4		±0.35	79		
3150	67.7		±0.31	83	-	
4000	69.5		±0.49		-	
5000	71.0		±0.35			
6300	70.8	†				
8000	71.5	†				
10000	67.0	†				
Total defic	28					
STC contour [ASTM E413] 61						

<sup>†</sup> Actual transmission loss of specimen may be higher than measured at this frequency band. Signal-to-noise in the receiving room less than 5 dB, therefore the result is "an estimate of the lower limit".

‡ Actual transmission loss of specimen may be higher than measured at this frequency band. Result within 10 dB of flanking limit found in separate study, therefore the result may be "potentially limited by the laboratory" due to flanking around the specimen.

Note: 95% Confidence from room qualification data. Flanking Limit from chamber flanking measurements. Data available upon request. Extended frequency results below 80Hz and above 5000Hz for reference only.





OL06-0942

Orfield Laboratories Inc

# APPENDIX C: SPECIMEN ASSEMBLY DESCRIPTION

The following table shows the elements in the wall assembly, with the source-room-side element first and the receiving-room-side element last.

Overall Mass = 630.0 lb [285.8 kg]
Overall Surface Density = 9.77 PSF [47.69 kg/m²]

	M	ass	Surf. Dens.	
Element	lb	[kg]	PSF	[kg/m²]
0.625" (5/8") gypsum drywall;				
2" Screws @ 12" O.C.	297.0	[134.7]	4.62	[22.54]
Green Glue @ 58 oz. (2 tubes) per 4x8 sheet				
(116 oz. total)				
0.625" (5/8") gypsum drywall				
3-5/8" 25 gauge steel studs @ 24" O.C.	23.0	[10.4]	0.36	[1.75]
3.5" R13 glass fiber batts	16.0	[7.3]	0.25	[1.21]
0.625" (5/8") gypsum drywall				
Green Glue @ 58 oz. (2 tubes) per 4x8 sheet				
(116 oz. total)				
0.625" (5/8") gypsum drywall;				
2" Screws @ 12" O.C.	294.0	[133.4]	4.57	[22.31]

All materials were weighed prior to installation. Weights of fasteners are not represented in the above totals.

#### **FRAMING**

A 3-5/8" wide steel track was laid on the floor and a 3-5/8" wide steel track was bolted to the top frame in the specimen opening. Steel 3-5/8" studs were fastened to the bottom and top tracks, spaced 24" apart, on-centers. The outermost steel 3-5/8" studs were also bolted to each side of the specimen opening frame.

#### **INSULATION**

Insulation was R13 glass-fiber un-faced batt measuring 23" wide and 3.5" thick. Batts were friction-fit into each entire stud cavity.

#### SHEETING

The Green Glue adhesive was pre-laminated into sandwiches, between two gypsum board panels. Each sandwich was assembled by the client off-site. According to the client, Green Glue was applied from two entire 29 oz. adhesive cartridges in a random pattern over one whole gypsum board panel. A second sheet of gypsum board was applied to the adhesive. The sandwich was thoroughly compressed by methodically walking over the entire face.



OL06-0942

Test

Orfield Laboratories Inc



Figure 1: Typical Green Glue Application (photo by client)

The adhesive aged from the assembly date, August 17 according to the client, to the test date, September 29. This is more than the 14 days period stated in ASTM Standard E90 for water-based laminating adhesives.

Sandwiches were fastened to the studs on each side with 2" drywall screws, spaced 12" apart, driven through both layers of gypsum board at once. The seams were sealed with 1/8" strips of rope-caulk.

Panels were shimmed at installation so equal gaps were at the top and bottom. Gaps were less than ½" in all cases. Shims were removed after sheeting was fastened and the perimeter was sealed on the source and receiver room sides with 7/8" Mortite-brand rope-caulk.



Client Green Glue Company, L.L.C.

Test OL06-0942



of 8

#### APPENDIX D: SINGLE-NUMBER CALCULATION TO ISO 717-1

Freq. Band	$R_i$ $(R_i \equiv TL)$	Ref Curve	Unfav. Deviat.	L <sub>i1</sub> Spectrum	L <sub>i1</sub> - R <sub>i</sub> Level	L <sub>i2</sub> Spectrum	L <sub>i2</sub> - R <sub>i</sub> Level
(Hz)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)
50	20.0						
63	19.9						
80	24.4						
100	30.7	40	9.3	-29.0	-59.7	-20.0	-50.7
125	37.4	43	5.6	-26.0	-63.4	-20.0	-57.4
160	42.8	46	3.2	-23.0	-65.8	-18.0	-60.8
200	47.7	49	1.3	-21.0	-68.7	-18.0	-65.7
250	50.9	52	1.1	-19.0	-69.9	-15.0	-65.9
315	53.1	55	1.9	-17.0	-70.1	-14.0	-67.1
400	55.6	58	2.4	-15.0	-70.6	-13.0	-68.6
500	59.6	59	-	-13.0	-72.6	-12.0	-71.6
630	61.7	60	-	-12.0	-73.7	-11.0	-72.7
800	63.5	61	-	-11.0	-74.5	-9.0	-72.5
1000	64.7	62	-	-10.0	-74.7	-8.0	-72.7
1250	66.4	63	-	-9.0	-75.4	-9.0	-75.4
1600	65.9	63	-	-9.0	-74.9	-10.0	-75.9
2000	64.7	63	-	-9.0	-73.7	-11.0	-75.7
2500	66.4	63	-	-9.0	-75.4	-13.0	-79.4
3150	67.7	63	-	-9.0	-76.7	-15.0	-82.7
4000	69.5						
5000	71.0						
		Sum =	24.8	R <sub>A,1</sub> =	56.0	R <sub>A,2</sub> =	49.1
		$R_W =$	59	C =	-3	$C_{tr} =$	-10

Note: The calculations in ISO 717-1 are performed based on assumed equivalency of the ASTM and the corresponding ISO test methods. The test herein is performed according to ASTM standards.

The spectrum adaptation terms C and  $C_{tr}$  characterize performance against two specific sound sources, A-weighted pink noise and A-weighted traffic noise respectively. The standard ISO 717-1 includes a discussion of "Use of Spectrum Adaptation Terms" in Annex A (informative).

Each spectrum adaptation term may additionally be reported with extended frequency bands included. A calculation for the primary frequency range is shown above, but all available extended-frequency calculations were performed to compare against corresponding ratings of other specimens.

$$R_{w}(C; C_{tr}) = 59 (-3; -10)$$

$$R_{w}(C; C_{tr}; C_{50-3150}; C_{tr,50-3150}) = 59 (-3; -10; -8; -20)$$

$$R_{w}(C; C_{tr}; C_{100-5000}; C_{tr,100-5000}) = 59 (-3; -10; -2; -10)$$

$$R_{w}(C; C_{tr}; C_{50-5000}; C_{tr,50-5000}) = 59 (-3; -10; -7; -20)$$

